



FX-III Jet Set Stabilizes Soil and Waterproofs Perimeter of the Steiff Building, a Baltimore Landmark



Three quarter inch diameter steel pipes are driven into the ground 8' – 10' ft deep along the front wall of the building. The pipes are spaced on 3' – 4' centers.



FX-III Jet Set is pumped through the pipes. The pipes are raised out of the ground in one foot intervals until the pumping is completed.

(over)



Gauges on the pump hoses allow the technicians to monitor the FX-III Jet Set during the pumping process.



After all pipes have been pumped and removed, the pipe holes are patched with FX-922 Plug & Fast Set.